

APPENDIX V – TVA ENVIRONMENTAL QUALITY PROTECTION SPECIFICATIONS FOR TRANSMISSION LINE CONSTRUCTION

1. General – Tennessee Valley Authority (TVA) and/or the assigned contractor shall plan, coordinate, and conduct operations in a manner that protects the quality of the environment and complies with TVA's environmental expectations discussed in the preconstruction meeting. This specification contains provisions that shall be considered in all TVA and contract construction operations. If the contractor fails to operate within the intent of these requirements, TVA will direct changes to operating procedures. Continued violation will result in a work suspension until correction or remedial action is taken by the contractor. Penalties and contract termination will be used as appropriate. The costs of complying with the Environmental Quality Protection Specifications are incidental to the contract work, and no additional compensation will be allowed. At all structure and conductor pulling sites, protective measures to prevent erosion will be taken immediately upon the end of each step in a construction sequence, and those protective measures will be inspected and maintained throughout the construction and right-of-way rehabilitation period.
2. Regulations - TVA and/or the assigned contractor shall comply with all applicable Federal, state, and local environmental and antipollution laws, regulations, and ordinances related to environmental protection and prevention, control, and abatement of all forms of pollution.
3. Use Areas - TVA and/or the assigned contractor's use areas include but are not limited to site office, shop, maintenance, parking, storage, staging, assembly areas, utility services, and access roads to the use areas. The construction contractor shall submit plans and drawings for their location and development to the TVA engineer and project manager for approval. Secondary containment will be provided for fuel and petroleum product storage pursuant to 29CFR1910.106(D)(6)(iii)(OSHA).
4. Equipment - All major equipment and proposed methods of operation shall be subject to the approval of TVA. The use or operation of heavy equipment in areas outside the right-of-way, access routes, or structure, pole, or tower sites will not be permitted without permission of the TVA inspector or field engineer. Heavy equipment use on steep slopes (greater than 20 percent) and in wet areas will be held to the minimum necessary to construct the transmission line. Steps will be taken to limit ground disturbance caused by heavy equipment usage, and erosion and sediment controls will be instituted on disturbed areas in accordance with state requirements.

No subsurface ground-disturbing equipment or stump-removal equipment will be used by construction forces except on access roads or at the actual structure, pole, or tower sites, where only footing locations and controlled runoff diversions shall be created that disturb the soil. All other areas of ground cover or in-place stumps and roots shall remain in place. (Note: Tracked vehicles disturb surface layer of the ground due to size and function.) Some disking of the right-of-way may occur for proper seedbed preparation.

Unless ponding previously occurred (i.e., existing low-lying areas), water should not be allowed to pond on the structure sites except around foundation holes; the water must be directed away from the site in as dispersed a manner as possible. At tower or structure sites, some means of upslope interruption of potential overland flow and diversion around the footings should be provided as the first step in construction-site preparation. If leveling

is necessary, it must be implemented by means that provide for continuous gentle, controlled, overland flow or percolation. A good grass cover, straw, gravel, or other protection of the surface must be maintained. Steps taken to prevent increases in the moisture content of the in-situ soils will be beneficial both during construction and over the service life of any structure.

5. Sanitation - A designated TVA or contractor representative shall contact a sanitary contractor who will provide sanitary chemical toilets convenient to all principal points of operation for every working party. The facilities shall comply with applicable Federal, state, or local health laws and regulations. They shall not be located closer than 100 feet to any stream or tributary or to any wetland. The facilities shall be required to have proper servicing and maintenance, and the waste disposal contractor shall verify in writing that the waste disposal will be in state-approved facilities. Employees shall be notified of sanitation regulations and shall be required to use the toilet facilities.
6. Refuse Disposal - Designated TVA and/or contractor personnel shall be responsible for daily inspection, cleanup, and proper labeling, storage, and disposal of all refuse and debris produced by his operations and by his employees. Suitable refuse collecting facilities will be required. Only state-approved disposal areas shall be used. Disposal containers such as dumpsters or roll-off containers shall be obtained from a proper waste disposal contractor. Solid, special, construction/demolition, and hazardous wastes as well as scrap are part of the potential refuse generated and must be properly managed with emphasis on reuse, recycle, or possible give away, as appropriate, before they are handled as waste. Contractors must meet similar provisions on any project contracted by TVA.
7. Landscape Preservation - TVA and its contractors shall exercise care to preserve the natural landscape in the entire construction area as well as use areas, in or outside the right-of-way, and on or adjacent to access roads. Construction operations shall be conducted to prevent any unnecessary destruction, scarring, or defacing of the natural vegetation and surroundings in the vicinity of the work.
8. Sensitive Areas Preservation - Certain areas on site and along the right-of-way may be designated by the specifications or the TVA engineer as environmentally sensitive. These areas include but are not limited to areas classified as erodible, geologically sensitive, scenic, historical and archaeological, fish and wildlife refuges, water supply watersheds, and public recreational areas such as parks and monuments. Contractors and TVA construction crews shall take all necessary actions to avoid adverse impacts to these sensitive areas and their adjacent buffer zones. These actions may include suspension of work or change of operations during periods of rain or heavy public use; hours may be restricted or concentrations of noisy equipment may have to be dispersed. If prehistoric or historic artifacts or features are encountered during clearing or construction operations, the operations shall immediately cease for at least 100 feet in each direction, and TVA's right-of-way inspector or construction superintendent and Cultural Resources Program shall be notified. The site shall be left as found until a significance determination is made. Work may continue elsewhere beyond the 100-foot perimeter.
9. Water Quality Control - TVA and contractor construction activities shall be performed by methods that will prevent entrance or accidental spillage of solid matter, contaminants, debris, and other objectionable pollutants and wastes into flowing caves, sinkholes, streams, dry watercourses, lakes, ponds, and underground water sources.

The clearing contractor will erect and (when TVA or contract construction personnel are unable) maintain Best Management Practices (BMPs) such as silt fences on steep slopes and adjacent to any stream, wetland, or other water body. Additional BMPs may be required for areas of disturbance created by construction activities. BMPs will be inspected by the TVA field engineer or other designated TVA or contractor personnel routinely and during periods of high runoff, and any necessary repairs will be made as soon as practicable. BMP inspections will be conducted in accordance with permit requirements. Records of all inspections will be maintained on site, and copies of inspection forms will be forwarded to the TVA construction environmental engineer.

Acceptable measures for disposal of waste oil from vehicles and equipment shall be followed. No waste oil shall be disposed of within the right-of-way, on a construction site, or on access roads.

10. Turbidity and Blocking of Streams - Construction activities in or near SMZs or other bodies of water shall be controlled to prevent the water turbidity from exceeding state or local water quality standards for that stream. All conditions of a general storm water permit, aquatic resource alteration permit, or a site-specific permit shall be met including monitoring of turbidity in receiving streams and/or storm water discharges and implementation of appropriate erosion and sediment control measures.

Appropriate drainage facilities for temporary construction activities interrupting natural site drainage shall be provided to avoid erosion. Watercourses shall not be blocked or diverted unless required by the specifications or the TVA engineer. Diversions shall be made in accordance with TVA's "A Guide for Environmental Protection and Management Practices for Tennessee Valley Authority Transmission Construction and Maintenance Activities."

Mechanized equipment shall not be operated in flowing water except when approved and, then, only to construct crossings or to perform required construction under direct guidance of TVA. Construction of stream fords or other crossings will only be permitted at approved locations and to current TVA construction access road standards. Material shall not be deposited in watercourses or within stream bank areas where it could be washed away by high stream flows. Appropriate U.S. Army Corps of Engineers and state permits shall be obtained.

Wastewater from construction or dewatering operations shall be controlled to prevent excessive erosion or turbidity in a stream, wetland, lake, or pond. Any work or placing of equipment within a flowing or dry watercourse requires the prior approval of TVA.

11. Clearing - No construction activities may clear additional site or right-of-way vegetation or disturb remaining retained vegetation, stumps, or regrowth at locations other than the structure sites and conductor setup areas. TVA and the construction contractor(s) must provide appropriate erosion or sediment controls for areas they have disturbed that have previously been restabilized after clearing operations. Control measures shall be implemented as soon as practicable after disturbance in accordance with applicable Federal, state, and/or local storm water regulations.
12. Restoration of Site - All construction disturbed areas, with the exception of farmland under cultivation and any other areas as may be designated by TVA's specifications, shall be stabilized in the following manner unless the property owner and TVA's engineer specify a different method:

- A. The subsoil shall be loosened to a minimum depth of 6 inches if possible and worked to remove unnatural ridges and depressions.
 - B. If needed, appropriate soil amendments will be added.
 - C. All disturbed areas will initially be seeded with a temporary ground cover such as winter wheat, rye, or millet, depending on the season. Perennials may also be planted during initial seeding if proper growing conditions exist. Final restoration and final seeding will be performed as line construction is completed. Final seeding will consist of permanent perennial grasses such as those outlined in TVA's "A Guide for Environmental Protection and Management Practices for Tennessee Valley Authority Transmission Construction and Maintenance Activities." Exceptions would include those areas designated as native grass planting areas. Initial and final restoration will be performed by the clearing contractor.
 - D. TVA holds the option, depending upon the time of year and weather condition, to delay or withdraw the requirement of seeding until more favorable planting conditions are certain. In the meantime, other stabilization techniques must be applied.
13. Air Quality Control - Construction crews shall take appropriate actions to minimize the amount of air pollution created by their construction operations. All operations must be conducted in a manner that avoids creating a nuisance and prevents damage to lands, crops, dwellings, or persons.
14. Burning - Before conducting any open burning operations, the contractor shall obtain permits or provide notifications as required to state forestry offices and/or local fire departments. Burning operations must comply with the requirements of state and local air pollution control and fire authorities and will only be allowed in approved locations and during appropriate hours and weather conditions. If weather conditions such as wind direction or speed change rapidly, the contractor's burning operations may be temporarily stopped by the TVA field engineer. The debris for burning shall be piled and shall be kept as clean and as dry as possible, then burned in such a manner as to reduce smoke. No materials other than dry wood shall be open burned. The ash and debris shall be buried away from streams or other water sources and shall be in areas coordinated with the property owner.
15. Dust and Mud Control - Construction activities shall be conducted to minimize the creation of dust. This may require limitations as to types of equipment, allowable speeds, and routes utilized. Water, straw, wood chips, dust palliative, gravel, combinations of these, or similar control measures may be used subject to TVA's approval. On new construction sites and easements, the last 100 feet before an access road approaches a county road or highway shall be graveled to prevent transfer of mud onto the public road.
16. Vehicle Exhaust Emissions - TVA and/or the contractors shall maintain and operate equipment to limit vehicle exhaust emissions. Equipment and vehicles that show excessive emissions of exhaust gasses and particulates due to poor engine adjustments or other inefficient operating conditions shall not be operated until corrective repairs or adjustments are made.
17. Vehicle Servicing - Routine maintenance of personal vehicles will not be performed on the right-of-way. However, if emergency or "have to" situations arise, minimal/temporary

maintenance to personal vehicles will occur in order to mobilize the vehicle to an off-site maintenance shop. Heavy equipment will be serviced on the right-of-way except in designated sensitive areas. The Heavy Equipment Department within TVA or the construction contractor will properly maintain these vehicles with approved spill prevention controls and countermeasures. If emergency maintenance in a sensitive or questionable area arises, the area environmental coordinator or construction environmental engineer will be consulted. All wastes and used oils will be properly recovered, handled, and disposed/recycled. Equipment shall not be temporarily stored in stream floodplains, whether overnight or on weekends or holidays.

18. Smoke and Odors - TVA and/or the contractors shall properly store and handle combustible material that could create objectionable smoke, odors, or fumes. The contractor shall not burn refuse such as trash, rags, tires, plastics, or other debris.
19. Noise Control - TVA and/or the contractor shall take measures to avoid the creation of noise levels that are considered nuisances, safety, or health hazards. Critical areas including but not limited to residential areas, parks, public use areas, and some ranching operations will require special considerations. TVA's criteria for determining corrective measures shall be determined by comparing the noise level of the construction operation to the background noise levels. In addition, especially noisy equipment such as helicopters, pile drivers, air hammers, chippers, chain saws, or areas for machine shops, staging, assembly, or blasting may require corrective actions when required by TVA.
20. Noise Suppression - All internal combustion engines shall be properly equipped with mufflers as required by the Department of Labor's "Safety and Health Regulations for Construction." TVA may require spark arresters in addition to mufflers on some engines. Air compressors and other noisy equipment may require sound-reducing enclosures in some circumstances.
21. Damages - The movement of construction crews and equipment shall be conducted in a manner that causes as little intrusion and damage as possible to crops, orchards, woods, wetlands, and other property features and vegetation. The contractor will be responsible for erosion damage caused by his actions and especially for creating conditions that would threaten the stability of the right-of-way or site soil, the structures, or access to either. When property owners prefer the correction of ground cover condition or soil and subsoil problems themselves, the section of the contract dealing with damages will apply.

Revision July 2003